

An Bord Pleanála
64 Marlborough Street
Dublin 1
DOI V902

17/04/2024

Re: ABP Ref. 318914-24, SID-WX-2024-003 - 110kV substation and 110kV underground grid connection in the townland of Great Island, Kilmokea, County Wexford. (kilmokeagreatislandsubstation.ie)

Dear Sir/Madam,

Further to correspondence received from An Bord Pleanála, dated March 21st 2024, and observations on the above application from the Department of Housing, Local Government and Heritage, and Transport Infrastructure Ireland “TII”, please see below a response to the items raised in these submissions that relate solely to the issues raised in observations received from these two prescribed bodies. The response is for the purposes of clarifying information submitted with the original application and, as such, is not additional technical information.

Department of Housing, Local Government and Heritage

In relation to the archaeological requirements set out in Points 1-4 of the submission from the Department of Housing, Local Government and Heritage, it is considered that Points 1,2 and 4 can be addressed by way of suitably-worded conditions attached to any forthcoming grant of permission.

With regard to Point 3, please see attached (Appendix 1) an updated version of the Construction and Environmental Management Plan (CEMP) submitted within the original application. As required by Point 3, the updated CEMP includes all likely archaeological impacts and mitigation measures proposed.

Further to a grant of planning permission by Wexford County Council (LPA Ref. 20231294) in January 2024 for development described as construction of a Battery Energy Storage System, 38kV substation and an underground grid connection to an existing 38kV substation, and in accordance with Condition 11 of this permission, an archaeological licence application, including a method statement, was submitted to the adjudicating authorities and a licence was subsequently

granted to carry out testing within the footprint of the proposed development (Licence No. Ref. 24E0413).

The development granted permission (LPA Ref. 20231294) includes all appropriate landscaping works and any other site works required to facilitate the electrical infrastructure permitted under the above permission and that proposed under this subject application (ABP-318914-24) as well as a further application to Wexford County Council for development described as construction of a 110kV Battery Energy Storage System (LPA Ref. 20240309). Findings from the test-trenching archaeological investigations permitted under the licence granted and referred to above will therefore also apply to this proposed development (Ref. ABP Ref. 318914-24, SID-WX-2024-003) and will be useful to inform any further archaeological requirements that may be conditioned as part of any forthcoming grant of permission.

Transport Infrastructure Ireland

In relation to points raised by TII, an addendum letter to the previously submitted Transport Management Plan has been prepared by Local Transport Projects Ltd. "LTP" attached in Appendix 2. In summary, the port of entry for any abnormal loads has been identified as Rosslare Harbour. In relation to potential impacts upon the road network, the letter highlights that loads associated with the proposed development are predicated to be less than those associated with the approved adjacent Greenlink Interconnector facility (ABP Ref: 308906). It is therefore expected that the same route from Rosslare Harbour would also be suitable for the proposed scheme in terms of the impact on structures along the route.

The letter also states that on behalf of the Applicant, LTP engaged with Wexford County Council Roads Department in August/September 2023 to ascertain their views on the proposed construction routing for electrical infrastructure development at Great Island, Kilmokea. This development includes other proposals recently granted planning permission and currently under consideration by Wexford County Council (LPA Refs. 20231294 and 20240309 respectively), and this proposal under consideration by an Bord Pleanála. In all instances no concerns regarding traversing structures or routing along the proposed regional/national roads as part of this application was raised.

This concludes the Applicant's response to submissions received from Prescribed Bodies for application ABP Ref. 318914-24, SID-WX-2024-003. I would be grateful if you would confirm receipt of this letter. If you require any further information or clarification please do not hesitate to

contact me.

Yours faithfully,



Paul O' Sullivan (Licentiate Member of the RTPI)

Entrust Ltd,
Unit 1D Deerpark Business Centre, Oranmore,
Co. Galway.
H91 X599
Tel: +353 (0)91 342 511
Email: paul@entrust-services.com

Appendix 1 -

**Construction and Environmental Management Plan –
prepared by IE Consulting Ltd. (updated following Prescribed
Bodies comments from Transport Infrastructure Ireland**

Kilmannock Battery Storage Ltd

Construction Environmental Management Plan

Great Island, Kilmokea, Co. Wexford



December 2023

Construction Environmental Management Plan

Client: Kilmannock Battery Storage Ltd

Location: Great Island, Kilmokea, Co. Wexford

Date: 13th December 2023

Copyright © IE Consulting 2023

This report or its contents must not be reproduced for any purpose without written permission. It is to be used only for the purpose for which it is supplied. In any event, IE Consulting accepts no responsibility for any costs, liabilities or losses arising as a result of the use of or reliance upon the contents of this report by any person other than the client as identified above.

Document Control

PROJECT NUMBER: IE2816		DOCUMENT REF: IE2816_Report_5937			
5.0	ISSUE-03	LMc	PMS	JK	15-04-2023
4.0	ISSUE-02	LMc	PMS	JK	15-12-2023
3.0	ISSUE-01	LMc	PMS	JK	14-12-2023
2.0	DRAFT-02	LMc	PMS	JK	13-12-2023
1.0	DRAFT-01	LMc	PMS		21-11-2023
Revision	Purpose Description	Originated	Checked	Reviewed	Date

Contents

1.	Introduction	1
2.	Proposed Site Description	2
2.1.	General Hydrological, Hydrogeological and Ecological Setting	2
2.2.	Proposed Construction Programme – Sequencing of Work	5
2.3.	Project Operational Lifespan	5
3.	Objectives	6
4.	Potential Sources of Pollution	6
5.	Potential Pollution Receptors	7
6.	Pre-Construction Pollution Mitigation Measures & Environmental Control	8
6.1.	Pre-Construction Pollution Mitigation Measures	8
6.1.1.	Temporary Construction Works Compound and Designated Storage Areas	8
6.2.	Construction Stage Environmental Mitigation Plan	10
6.2.1.	Site Preparation Works	10
6.2.2.	Existing Site Entrance and Internal Access Road	10
6.2.3.	110kV Substation Building	11
6.2.4.	IPP Building	11
6.2.5.	Trenching Methodology	11
6.2.6.	Dust Minimisation	12
6.2.7.	Control of Noise	14
6.2.8.	Protection of Soil, Surface Waters and Groundwater During Construction Stage	14
6.2.9.	Protection of Flora and Fauna	16
6.2.10.	Refuelling	18
6.2.11.	Site Tidiness & Housekeeping	19
6.2.12.	Inspection & Environmental Control & Monitoring	19
6.2.13.	Wastewater Management Plan	21
6.2.14.	Training and Toolbox Talks	21
6.2.15.	Biosecurity Invasive Species Best Practice Measures	22
6.3.	Construction Stage Waste Management	23
6.4.	Operational Controls	23
6.5.	Drain & Watercourse Management Plan	23
6.6.	Archaeology	24
6.7.	Cultural Heritage – Landscape & Visual	26
7.	Decommissioning Process, Site Restoration and Monitoring Program	27
7.1.	Decommissioning Process and Time Scale	27
7.2.	Site Restoration	31
7.3.	Monitoring Programme	33
7.4.	Inspection	33
8.	Summary Conclusions & Recommendations	34
9.	References	35

Appendices

Appendix A. Drawings

Appendix B. Typical Wheel Wash Details

Appendix C. Archaeological Testing – Method Statement

1. Introduction

IE Consulting was requested by Entrust Planning and Environmental, on behalf of Kilmannock Battery Energy Storage Ltd, to undertake a preliminary planning stage Construction Environmental Management Plan (CEMP) for a proposed development at Great Island, Co. Wexford.

The development as proposed comprises the construction of an electrical infrastructure installation and associated underground grid connection (UGC) on lands within the townland of Great Island measuring approximately 2.58Ha./25812 square metres in overall area. The installation would consist of an 110kV tailfed substation and underground grid connection measuring approximately 838m in overall length. The 110kV substation would consist of an 110kV transformer; house transformer; disconnect, individual current and voltage transformers, combined current/voltage transformer, surge arrestors; circuit breakers and cable sealing end; a blastwall measuring 8.00m in overall height; 4no. lightning masts measuring 18.00m in overall height; palisade fencing measuring 2.60m in overall height; pole-mounted security cameras and lamp posts. An Eirgrid substation building with an overall footprint of approximately 180.00sqm and overall height of 4.20m would be located at the western end of the substation area. An IPP substation with an overall footprint of 132sqm and height of overall 4.20m would be located at the eastern end. The typical UGC installation would consist of standard ESB ducting details of the following 1no. trench (0.82m wide; 1.31m deep) measuring approximately 838m in overall length to carry 3no. 160mm power ducts and 2no. communication ducts and an ECC duct, connecting the proposed substation to an existing 110kV Eirgrid substation at Great Island. The typical trefoil trench will need to be adapted to a flat formation to accommodate for any service crossings encountered along the route. A typical width of trench for a flat formation trench would be approx. 1.60m with varying depths. A temporary construction compound would be constructed within the site boundary for construction phase of the development, after which it would be removed.

The purpose of this CEMP is to identify and define the specific environmental aspects of the project, the measures that are to be put in place and the procedures to be followed for the duration of the construction works. The CEMP assesses key environmental features, including water, noise, ecology, dust and the potential of pollution during the construction and decommissioning phases of the development, and identifies potential pollution receptors and proposes suitable mitigation measures as necessary.

This CEMP has been undertaken in consideration of the following guidance documents:-

'CIRIA C532 – Control of Water Pollution from Construction Sites – Guidance for Consultants & Contractors' – CIRIA-2001'

Section 4 of this CEMP outlines the potential sources of pollution with *Section 5* identifying the potential receptors.

Section 6 details the Construction Plan for the site incorporating an inspection schedule to be implemented at pre-construction stage, construction stage and post construction stage.

Section 7 details the Decommissioning Phase for the site.

2. Proposed Site Description

2.1. General Hydrological, Hydrogeological and Ecological Setting

The site of the proposed development is located at Great Island, Co. Wexford.

The proposed development site is bounded to the north by an area of undeveloped land and the Rosslare to Wexford railway line, to the east and south-east by agricultural lands and to the south-west and west by the Great Island Power Station facility site. The total area of the site of the proposed development is approximately 2.58 hectares.

The location of the site of the proposed development is illustrated on *Figure 1* below and is shown on *Drawing Number IE2816-001-C, Appendix A*.




Figure 1 – Site Location

As illustrated in *Figure 1* above, the most immediate and significant hydrological features in the vicinity of the site of the proposed development are the River Barrow Estuary, which flows in a north to south direction approximately 253m beyond the western boundary of the site, the River Suir Estuary, which flows in a north to south direction approximately 255m beyond the western boundary of the site, the Campile River, which flows in an east to west direction approximately 914m beyond the southern boundary of the site and the Newtown Stream, which flows in a north to south direction 132m beyond the eastern boundary of the site.

The catchment area of the River Barrow Estuary was delineated and found to be approximately 3,025km² to a point downstream of the site. An assessment of the River Barrow Estuary upstream catchment area indicates that the catchment is predominantly rural in nature with the urban fraction in the upstream catchment area accounting for 1.6% of the total catchment area.

The catchment area of the River Suir Estuary was delineated and found to be approximately 3,520km² to a point downstream of the site. An assessment of the River Suir Estuary upstream catchment area indicates that the catchment is predominantly rural in nature with the urban fraction in the upstream catchment area accounting for 0.8% of the total catchment area.

The catchment area of the Campile River was delineated and found to be approximately 28.213km² to a point downstream of the site. An assessment of the Campile River upstream catchment area indicates that the catchment is predominantly rural in nature with the urban fraction in the upstream catchment area accounting for 0.1% of the total catchment area.

The catchment area of the Newtown Stream was delineated and found to be approximately 7.173km² to a point downstream of the site. An assessment of the Newtown Stream upstream catchment area indicates that the catchment is predominantly rural in nature with the urban fraction in the upstream catchment area accounting for 0.1% of the total catchment area.

There are no other significant natural fluvial watercourses or hydrological features mapped within or immediately adjacent to the boundary of the site.

The bedrocks underlying the location of the proposed development are part of the Campile Formation that are characterised as Rhyolitic volcanic grey and brown slates, which comprise bedrock aquifers that are classified as Regionally Important Aquifer-fissured bedrock. Regionally Important Aquifer-fissured tend to comprise bedrock which is cable of supplying regionally important abstractions.

The GSI classifies vulnerability of the bedrock aquifer underlying the location of the proposed development as ranging from Extreme (E) to Extreme (X) vulnerability. Groundwater vulnerability is a term used to represent the intrinsic geological and hydrogeological characteristics that determine the ease with which groundwater may be contaminated by human activities. Where the subsoil thickness is 0-3 m, the vulnerability is rated as Extreme (depending on the nature and thickness of the subsoil).

A detailed map of all of the hydrological features at and in the immediate vicinity of the proposed development site is presented on *Drawing Number IE2816-CEMP-102-B, Appendix A*.

There are no significant sensitive hydrogeological or groundwater features or resources within or in the immediate vicinity of the sites of the proposed development, such as public or group groundwater supply sources. Existing properties in the vicinity of the proposed development are supplied either via public mains supply or via individual private wells.

Mitigation measures are discussed in *Section 6* of this CEMP to ensure that there are no adverse negative impacts on the existing hydrological, hydrogeological and ecological features within and in the vicinity of the sites of the proposed development. This CEMP is primarily presented in consideration of the proposed 110kV substation development site. The proposed grid connection route is not located adjacent to any surface watercourses and does not transfer any surface watercourses, therefore it is considered specific CEMP requirements relative to the proposed grid connection works are not required.

In addition to the mitigation measures listed in this CEMP, the project shall incorporate and adopt all mitigation measures listed in the accompanying Ecological Impact Statement (Moore Group Environmental Services – September 2023).

2.2. Proposed Construction Programme – Sequencing of Work

The proposed 110kV Substation development will consist of the construction of the following;

- Route preparation and clearance (only where necessary);
- Widening of site entrance and access road (only where necessary);
- Construction of internal access road;
- Construction of Stone Areas;
- Site preparation and clearance (only where necessary);
- Erection of security fencing/perimeter fencing and CCTV;
- Setting up a secure construction compound within the development site;
- Setting up low voltage feed to construction compound;
- Trenching, ducting and DC cable laying;
- Construction of 110kV Substation Building
- Installation of 110kV Substation;
- Backfilling trenching;
- Commissioning and testing;
- Decommissioning and Site restoration.

2.3. Project Operational Lifespan

The proposed development is anticipated to have an operational lifespan of approximately 40 years. Following this lifespan there are two possible scenarios that can be considered, subject to gaining the relevant approvals and agreement from the appropriate parties and regulatory authorities;

1. The infrastructure may be upgraded or replaced and continue operation for a further specified timeframe;
2. The infrastructure may be left in-situ for future development, as the technology advances, at a future unknown date, or alternatively;
3. The infrastructure will be decommissioned and the site will be restored and rehabilitated.

3. Objectives

The objective of this preliminary CEMP is:

- To identify the specific environmental aspects of the project and implement specific mitigation measures, environmental controls and procedures to be followed for the duration of the construction works;
- To provide detailed proposals for site restoration following the decommissioning of activities at the sites of the proposed development.

4. Potential Sources of Pollution

The potential sources of pollution which may arise during the construction phase of the proposed development are summarised below:-

Construction Phase

- Stripping of overburden material within the proposed areas of site works, the construction compound and to create an access route within the development site; Stripping of overburden is to be kept to the very minimum.
- Cut and fill earthworks within the area of the proposed 110kV Substation
- Stockpiling of minimal volumes of overburden material (sub-soils, gravel, etc.);
- Excavation works for construction of foundations and trenches for the laying of ducts and cables;
- Stockpiling of specific building materials (sand, crushed stone, etc);
- Concreting works;
- Construction equipment on-site (fuel, leaks, etc);
- Storage of fuel on-site;
- Vibration, from the machinery (excavation and construction equipment).

Operational Phase

- On-going maintenance and management of the 110kV substation facility;
- Clearing areas within the site (vegetation);
- Storage of materials on-site (spare parts, etc);
- Inspection and Maintenance of 110kV substation facility;

Decommissioning and Restoration

The proposed development will consist of the decommissioning and site restoration of the following;

- Disassembling of substation and other electrical equipment;
- Breaking up of any concrete foundations and removal from site;
- Excavation works for construction of trenches for the removal of poles, ducts and cables;
- Backfilling trenching;
- Removal of security fencing/perimeter fencing;
- Removal of CCTV poles and cameras;
- Reinstatement access route or road not required for other use to original conditions;
- Setting up a secure compound within the development site for the duration of the decommissioning phase for temporary storage – to be fully restored or remediated when the decommissioning of the facility is complete;
- Site restoration, landscaping and re-vegetation as required.

Decommissioning activities, particularly the removal of project components and materials could cause environmental effects similar to those of the construction phase. The Decommissioning phase of the facility is discussed in more detail in *Section 7 below*.

5. Potential Pollution Receptors

In consideration of the proposed 110kV substation development site and existing topography at the location of the proposed works, the primary and most immediate potential hydrological and hydrogeological pollution receptor is the underlying groundwater aquifer.

No other receptors such as turloughs or sinkholes were identified or are mapped within or in the immediate vicinity of the proposed development site.

The proximity of residential properties to the proposed development site is considered to be the primary potential noise pollution receptors.

6. Pre-Construction Pollution Mitigation Measures & Environmental Control

Construction of the proposed 110kV substation development is envisaged to commence once final planning permission has been obtained. The proposed total construction duration is approximately 16 months.

An Environmental Clerk of Works (ECoW) will complete routine inspections and monitoring of all construction activities and oversight of the mitigation measures in the EMP to ensure environmental compliance. A key function of the ECoW will be to provide first-hand onsite identification, direction for intervention and immediate resolution of environmental issues as they arise

A project ecologist will prepare subject specific management plans e.g. Surface Water Management Plan.

Reporting of all monitoring will be retained onsite with the Main Contractor or ECoW, or with the responsible specialist consultant.

The proposed potential pollution mitigation measures outlined below shall be implemented in accordance with;

- *'CIRIA C532 – Control of Water Pollution from Construction Sites – Guidance for Consultants & Contractors' – CIRIA-2001.*
- *'CIRIA C648 – Control of Water Pollution from Linear Construction Projects – Technical Guidance – CIRIA 2006'*
- *Waste Management Act, 1996*
- *Best Practice Guidelines on the Preparation of Waste Management Plans for Construction & Demolition Projects. 2006*

6.1. Pre-Construction Pollution Mitigation Measures

Prior to the undertaking of any construction works associated with the proposed 110kV development the following pollution mitigation measures shall be implemented:-

6.1.1. Temporary Construction Works Compound and Designated Storage Areas

A temporary construction works compound with designated areas for the storage of building materials (sand, cement, additives, etc.), plant machinery and for delivery of materials shall be provided within the overall 110kV substation development site.

The general location of the temporary construction works compound is illustrated on *Drawing Number IE2816-CEMP-102-B, Appendix A.*

The proposed layout and general arrangement of the temporary construction works compound is illustrated on *Drawing Number IE2816-CEMP-104-A, Appendix A*.

The temporary works compound area shall be temporarily re-surfaced by placing a geotextile membrane onto the existing surface onto which a 200mm hardcore surface shall be placed. All hardcore surface areas shall be underlain by a simple drainage system that shall divert and discharge any surface water runoff to a drainage outfall point as illustrated on *Drawing Number IE2816-CEMP-104-A, Appendix A*. A small temporary 0.5m wide x 0.5m high earthen bund shall be formed along the boundary of the works compound.

The location of the temporary works compound is proposed as it allows for easy access to the site with minimum disruption to the nearby commercial operations.

As illustrated on *Drawing Number IE2816-CEMP-104-A, Appendix A*, the following elements and designations shall be contained within the temporary construction work compound:-

- Diesel generator;
- Temporary site office – Portakabin or similar;
- Employee Parking;
- Portaloo' type toilet facilities with suitable welfare and washing facilities. Any wastewaters generated from the construction works compound shall be discharged to self-contained storage tanks and shall be removed via a licenced contractor to a suitable wastewater disposal facility. No wastewaters generated within the works compound shall discharge to surface watercourses or to ground;
- Bunded re-fuelling area. It is not proposed to store any fuel, oils or chemicals within the construction works compound areas or any other area within the site. Where re-fuelling of plant or machinery is required fuel will be delivered to site via a standard commercial fuel vehicle or a mobile fuel browser. Re-fuelling shall only be undertaken within the designated bunded re-fuelling area;
- Potable water supply to site office and welfare facilities to be provided by temporary on-site potable water storage tanks. A water tanker to supply water used for other purposes;
- Designated areas for gravel, subsoil, topsoil and sand stockpiling;
- Contractor lock-up facility;
- Wheel Wash System. As illustrated on *Drawing Number IE2816-CEMP-004-A, Appendix A*, a vehicular wheel wash system shall be installed at the main ingress and egress point to the construction works compound. All commercial vehicles entering and existing the works compound shall pass through the wheel wash system;
- The wheel wash system shall be a self-contained and recycling system – there shall be no discharge from the wheel wash system to any receiving watercourse or any other location within the site. Typical examples of the proposed wheel wash system are presented in *Appendix B*.

The above mitigation measures associated with the construction works compound shall remain in place until completion of all construction and commissioning works and shall be inspected on a regular basis by the on-site ecological supervisor.

6.2. Construction Stage Environmental Mitigation Plan

The construction of the 110kV substation facility and associated 110kV underground grid connection forms part of a wider electrical infrastructure installation comprising a 110kV Battery Energy Storage System (BESS) and 38kV BESS, substation and underground grid connection that are subject to different consent regimes. Engineering and landscaping works to prepare the site in its entirety were submitted to Wexford County Council under planning application Ref. 20231294.

6.2.1. Site Preparation Works

The site of the proposed 110kV substation facility currently slopes moderately from south-west to north-east. In order to provide suitable level ground platforms for the construction of the 110kV substation facility it is proposed to undertake cut and fill earthworks within the boundary of the site. The specific details of the proposed cut and fill earthworks are presented on the drawings and details prepared by TLI Group and submitted to Wexford County Council under planning application Ref. 20231294. Construction mitigation was submitted as part of this application. To avoid overlapping of grants of planning permission and any planning conditions arising, site preparation works have been limited in this application to those necessary for construction of the 110kV substation compound. The main elements of the construction stage works and proposed construction stage pollution mitigation measures and environmental controls are summarised below.

6.2.2. Existing Site Entrance and Internal Access Road

The proposed 110kV substation development will involve the construction of a 5m wide access road and entrance to the substation compound. The access road works will consist of excavation works and the construction of tarmac road surfaces. In consideration of the access road works, excavated subsoil material arising from the formation base of the road is expected to be inert in nature and where required will be utilised for general landscaping works within the overall site boundary.

Any excess subsoil material that cannot be utilised or reused within the site shall be disposed of at suitable licenced facility. Excavated subsoil material shall be inspected by the on-site ecological supervisor.

Any surface water runoff from the access road shall discharge to stoned areas.

6.2.3. 110kV Substation Building

As illustrated on the layout drawings the 110kV substation building structure shall primarily be constructed onto a concrete base placed above existing ground levels. The concrete base shall be supported on a 0.25m deep compacted hardcore formation base that shall be constructed below existing ground levels.

In consideration of the switchgear and control room building works, the total volume of excavated subsoil material arising from the formation base of the structure will be approximately 45m³.

It is expected that this subsoil material will be inert in nature and where required will be utilised for general landscaping works within the overall site boundary. Any excess subsoil material that cannot be utilised or reused within the site shall be disposed of at suitable licenced facility. Excavated subsoil material shall be inspected by the on-site ecological supervisor.

Concrete and cements required for the construction of the structure shall be brought to site by an external supplier as and when required. No mixing or production of concrete or cements shall take place on-site.

6.2.4. IPP Building

As illustrated on the layout drawings the IPP building structure shall primarily be constructed onto a concrete base placed above existing ground levels. The concrete base shall be supported on a 0.25m deep compacted hardcore formation base that shall be constructed below existing ground levels.

In consideration of the switchgear and control room building works, the total volume of excavated subsoil material arising from the formation base of the structure will be approximately 33m³.

It is expected that this subsoil material will be inert in nature and where required will be utilised for general landscaping works within the overall site boundary. Any excess subsoil material that cannot be utilised or reused within the site shall be disposed of at suitable licenced facility. Excavated subsoil material shall be inspected by the on-site ecological supervisor.

Concrete and cements required for the construction of the structure shall be brought to site by an external supplier as and when required. No mixing or production of concrete or cements shall take place on-site.

6.2.5. Trenching Methodology

This method of laying cables involves the excavation of a trench. Initially the trench width will be marked with line marking spray paint, for the areas where the cables are to be placed. The width of the trench will vary depending on the number of cables running in parallel - it is anticipated that the width of the trench will range from 500mm to 1250mm.

To avoid extensive portions off ground being excavated at one time, a method of cut and cover will be used, whereby section by section of the site will be excavated; the cables are put in place; the trench backfilled, at a time.

A small excavator will be required to excavate a trench of depth 600mm. The topsoil (top 150mm) will be kept separate from other subsoil material. The excavated soil material can be temporarily placed along the side of the trench, the topsoil on one side of the trench and the other subsoil material on the other side of the trench.

The trench is then lined with a 100mm layer of sand, the cables are then placed along the trench, an additional 100mm layer of sand is used to cover the cables and then the trench is backfilled with the previously excavated material, first the subsoil material and finally the topsoil.

Any disturbance to the soil will require adequate backfilling and grading to match the contours of the surrounding land. If necessary the area will be reseeded or re-vegetated appropriately. Any surplus soil material will be removed to a designated storage area within the construction compound.

Care will be taken close to any watercourses. No excavated material will be placed near or within the buffer zone allocated to the Newtown Stream. This will prevent material or water runoff from entering the watercourse.

A minimum 15m buffer zone from defined natural watercourses will be maintained within the boundary of the site for any trenching and cabling works.

6.2.6. Dust Minimisation

- Overburden material shall only be stockpiled within a designated construction works compound area. This area is located beyond and is sufficiently distant from the Newtown Stream watercourse. Separate stockpiles will be designated for different materials.
- Stripped overburden material that is to be temporary stored shall be stockpiled to no more than 2m in height, to ensure anaerobic conditions do not occur and that the soil will remain fertile and capable of being re-seeded. All stockpiles on site will be covered with a waterproof cover to prevent mobilisation of the stockpile material.
- Excavated material arising from the construction of the existing access road widening, transformer enclosures, and internal access tracks will be temporarily stockpiled in the designated storage area for reuse within the site or appropriately categorised in accordance with the Waste Management Act, 1996 and European Waste Catalogue (EWC) codes and be disposed of at a licensed waste facility.
- Building materials (crushed stone, sand, etc) shall only be stockpiled within a designated area at the proposed temporary construction compound within the proposed site boundary and laid out to minimise exposure to wind. Sand and other aggregates will be stored in bunded areas and will not be allowed to dry out, unless this is required for a particular process. Water misting or sprays will be used as required if particularly dusty activities are necessary during dry or windy periods. Bulk cement and other fine powder materials will be delivered in enclosed tankers and stored in silos with suitable emission control systems to prevent escape of material and overfilling during delivery.

- No concrete production will take place on-site due to the sensitivity of the watercourses in the vicinity of the works. Concrete will be supplied to the site using ready mix lorries. No washing down of lorries or any other construction vehicles shall take place on-site.
- Where possible, concrete will be carefully placed by the use of a hydraulic pump to minimise the risk of concrete spillages. The ends of pump hoses will be secured during concreting to prevent the discharge hose accidentally depositing concrete away from the pour site.
- The delivery point for concrete will be within the bunded designated area. This will prevent potential concrete spillage from truck mixers contaminating the ground and leaching out into the groundwater. Compressors or generators used for connecting operations will be fitted with drip trays to collect fuel and oil spills that might otherwise contaminate the groundwater and lead to pollution of the watercourses.
- Concrete delivery vehicles will be precluded from washing out at or in the environs of the works, or at such location as would result in a discharge to surface waters.
- Site roads will be regularly cleaned and maintained as appropriate.
- Dry sweeping of large areas is to be avoided.
- Hard surface roads will be swept to remove mud and aggregate materials from their surface while any unsurfaced roads will be restricted to essential site traffic only.
- Any road with the potential to give rise to fugitive dust will be regularly watered, as appropriate, during dry and/or windy conditions.
- Vehicles using site roads will have speeds restricted where there is a potential for dust generation.
- Vehicles delivering material with dust potential to an off-site location will be enclosed or covered with tarpaulin at all times to restrict the escape of dust
- Access gates will be located at least 10m from receptors.
- Public roads outside the site will be regularly inspected for cleanliness, and cleaned as necessary. Before entrance onto public roads, trucks will be adequately inspected to ensure no potential for dust emissions.
- Inspection of onsite haul routes for integrity and instigation of necessary repairs to the surface will be effected as necessary. A record will be kept of all inspections of the haul routes and any subsequent action in a site log book.

6.2.7. Control of Noise

- Environmental Noise arising from activities on site will be controlled in accordance with the requirements of *British Standard BS5228* (refer to accompanying Noise Assessment Report which accompanies this planning application).
- The following noise control measures for generated noise shall be implemented during the construction works:
 - a. The hours of construction will be subject to the requirements and prior agreement with Wexford County Council.
 - b. All contractors will ensure that the plant and construction methods employed are the quietest available for the required purpose insofar as practicable.
 - c. Engines, vehicles and equipment will be switched off when not in use.
 - d. Machinery having rotating parts will be serviced according to supplier recommendations to prevent friction induced sound.
 - e. Site roads will be maintained in a clean condition and the site speed limit of 15 km/hr will be strictly adhered to.
 - f. Materials should be lowered, not dropped, insofar as practicable and safely.
 - g. Use of enclosures and screens around noise sources.
 - h. Liaison with the public

6.2.8. Protection of Soil, Surface Waters and Groundwater During Construction Stage

- All liquids, solids and powder containers will be clearly labelled and stored in sealable containers;
- All liquid and hazardous material will be stored in a designated and temporarily bunded area with appropriate signage. The temporary bunded area shall be located within the designated storage area located in the southern area of the site.
- There will be no discharge of effluent to groundwater or surface water during the construction phase. All wastewater from the construction facilities will be stored before removal off site for disposal and treatment – temporary portable toilet facilities only shall be used at the site.
- Spill kits will be provided in areas where liquids are stored and refuelling area.
- Contractors will be responsible for ensuring the regular maintenance of construction plant and equipment, to prevent leaks.

- A wheel wash system shall be provided at the main site exit location. The wheel wash shall be a self-contained or recycling type system and will not require any wash waters to be discharged to receiving water bodies at the site. All sludge collected within the wheel wash facility shall be removed via a vacuum type tanker and disposed off-site to a suitable licenced facility.
- Refuelling of plant during construction will not be carried out at the location of the proposed works but instead only within a designated refuelling area within the proposed temporary construction compound, the location of which is illustrated on *Drawing Number IE2816-CEMP-002-B ,Appendix A*. Only emergency breakdown maintenance will be carried out at the location of the works. The refuelling area will be furnished with fuel absorbent material and pads in the event of any accidental spillages.
- The fuel bowser/tank will be located on a level area in the construction compound when not in use and only designated trained and competent operatives will be authorised to refuel plant. Drip trays and spill kits will be kept available on site to ensure that any spills from vehicles are contained and removed off site. Fuels stored on site will be minimised. Any storage areas will be bunded appropriately for the fuel storage volume for the time period of the construction
- Spill kits will be available to deal with accidental spillages.
- A regular review of weather forecasts for heavy rainfall will be required and the contractor will be required to prepare a contingency plan for before and after such events.
- All materials shall be stored at the temporary compound and transported to the works zone immediately prior to construction;
- Weather conditions will be taken into consideration when planning construction activities to minimise risk of run off from site;
- If dewatering is required as part of the proposed works e.g. in wet areas, water will be treated prior to discharge;
- If very wet ground must be accessed during the construction process bog mats/aluminium panel tracks will be used to enable access to these areas by machinery. However, works will be scheduled to minimise access requirements during winter months;
- The contractor shall ensure that all personnel working on site are trained in pollution incident control response. A regular review of weather forecasts of heavy rainfall is required, and the Contractor is required to prepare a contingency plan for before and after such events;
- The contractor will carry out visual examinations of local watercourses from the proposed works during the construction phase to ensure that sediment is not above baseline conditions. In the unlikely event of water quality concerns, the Environmental Manager and ECoW will be consulted;
- Excavations will be left open for minimal periods to avoid acting as a conduit for surface water flows.
- Concrete or potential concrete contaminated water run-off will not be allowed to enter any watercourses. Any pouring of concrete (delivered to site ready mixed) will only be carried out in dry weather. Washout of concrete trucks shall not be permitted on site.

- Entry by plant equipment, machinery, vehicles and construction personnel into watercourses or wet drainage ditches shall not be permitted. All routes used for construction traffic shall be protected against migration of soil or wastewater into watercourses;
- Cabins, containers, workshops, plant, materials storage and storage tanks shall not be located near any surface water channels and will be located beyond the 50m hydrological buffer at all times.
- The delivery point for concrete will be within the bunded designated construction compound areas. Any compressors or generators used for connecting operations will be fitted with drip trays to collect any potential fuel and oil spills.
- Concrete washing of machines will take place off-site at an appropriate dedicated wash facility that will pose no threat to surface waters.
- A surface water management plan will be developed to minimise potential impacts on surrounding or downstream watercourses during construction or operation. The design of the surface water management plan will maintain the existing drainage regime as reasonably as possible. Drainage design, earthworks and environmental measures shall at all times ensure that the water quality and water levels of the on-site drainage channels are not adversely affected. Construction of the site drainage system will only be carried out during periods of low rainfall, and therefore minimum runoff rates.
- Where the removal of woody vegetation is required to facilitate the proposed development, vegetation removal will, where possible, take place outside the bird breeding season (March to August inclusive). Woody vegetation clearance will only occur during the breeding season following surveys which confirm the absence of breeding birds. In instances where nest sites are identified then clearance will not take place until the nest is vacated.

6.2.9. Protection of Flora and Fauna

There shall be on-going monitoring of wildlife in the vicinity of the construction works and any unusual species, dead species or damaged habitats should be reported immediately to the Construction Manager and/or Environmental Officer. This will be co-ordinated with the appointed Ecologist for the project.

Please refer to the accompanying NIS for further details. The spread and introduction of invasive species and noxious weeds will be avoided by adopting appropriate mitigation measures as per guidance issued by the NRA (2010) and the Irish Water Guidance (2016).

Where unexpected ecological habitats are uncovered the habitats protection protocol will be adhered to by site contractors.

Protection Protocol

This protocol is designed to ensure that ALL persons working on the construction works are fully aware of their legal obligations under the Wildlife Act 1976, as amended.

This Act affords protection to a range of wildlife in Ireland including wild birds, animals and plants. Whilst the project has received permission from the Government to proceed, this does not override certain laws that prevent wilful harm to protected species.

The following is applicable to the proposed 110kV substation development site:-

- Weather conditions shall be considered during all construction operations and no plant will enter within 100 metres of the Newtown Stream during or following heavy rain or other conditions likely to lead to large-scale or additional water flow that would carry soil or silt into the watercourses.
- Any removal of scrub, hedgerow or delimiting required will be carried out outside of the bird breeding season (1st March to 31st August inclusive).
- Contractors may discover bat roosts and if any bats are found, the Construction Manager and/or Environmental Officer are to be contacted immediately.
- Prior to arrival on site, contractor's vehicles and equipment will be thoroughly cleaned and then dried using high-pressure steam cleaning, with water >65 °C, in addition to the removal of all vegetative material. Items difficult to soak/spray will be wiped down with a suitable disinfectant (e.g. solution of 1% Virkon® Aquatic);
- Evidence that all machinery has been cleaned will be required to be on file for review by the statutory authorities. The level of evidence required of the Contractor will be actual registration plates of vehicles onsite and a register of when, how and where each of these were cleaned before they arrived on site;
- Visual inspections will be carried out on all machinery and equipment for evidence of attached plant or animal material, or adherent mud or debris. Any attached or adherent material will be removed before entering or leaving the site, securely stored (away from traffic) for removal to an appropriate waste storage area the end of the work day;
- No removed material or run-off will be allowed to enter a water body of any sort;
- Following cleaning, all equipment and vehicles will be visually inspected to ensure that all adherent material and debris has been removed manually;
- Each field vehicle must carry a 'disinfection box'. This will contain Virkon Aquatic or another proprietary disinfectant, a spraying mechanism, cloths or sponges, a scrubbing brush and protective gloves. Protective gloves must be worn when using any disinfectant solution;
- Records of supplies and cleaning of delivery vehicles will be kept and regularly inspected by the ECoW;
- Spot checks on the adequacy of cleaning will be carried out by the ECoW;

- It is recommended to apply disinfectant to the undercarriage and wheels of any vehicles used after cleaning if the vehicles have been used in streams or rivers. (This does not apply to vehicle or machinery use in wetlands or peatland areas). Disinfectants must be used strictly in accordance with the manufacturer's instructions. They must be disposed of safely and never close to open waters such as drains etc.
- For any material entering the site, the supplier must provide an assurance that it is free of invasive species;
- Ensure all site users are aware of invasive species management plan, biosecurity and treatment methodologies. This can be achieved through "toolbox talks" before works begin on the site;
- Adequate site signage, hoarding and fencing will be erected in relation to the management of non-native invasive species.

Procedure for Protection of Potential Bat Roosts

Whilst no bat roosts are expected at this location, there is a chance that bats could occupy roosts prior to the commencement of works. If bat roosts or bats are found during site clearance, works will cease and the National Parks and Wildlife Service (NPWS) will be contacted to avoid an offence being committed by disturbing a bat roost. Works will be suspended if bats are found to avoid further risk of direct harm to bats.

Landscaping with native species within the project location is suggested. This vegetation will be planted to maintain the nutrient quality of the soil and manage weed growth. The project location will be returned to its original or future anticipated land use after decommissioning.

6.2.10. Refuelling

- Construction plant and equipment shall only be parked over-night within the proposed temporary construction compound, the location of which is illustrated *on Drawing Number IE2816-CEMP-102-B, Appendix A*. Construction plant and equipment shall be checked daily for any visual signs of oil or fuel leakage, as well as wear and tear.
- Fuel will not be stored on-site for the duration of the construction phase. Fuel will only be brought to site via a mobile double skinned fuel bowser. For any liquid other than water, this shall include storage in suitable tanks and containers which shall be housed in the designated area surrounded by bund walls of sufficient height and construction so as to contain 110 per cent (110%) of the total contents of all containers and associated pipework. The floor and walls of the bunded areas shall be impervious to both water and oil. The pipes should vent downwards into the bund.
- All liquids, solids and powder containers will be clearly labelled and stored in sealable containers.

- Where contractors are required to refuel vehicles on-site, this will be carried out at the designated refuelling location by competent personnel. All refuelling areas will be on areas of hard standing at designated areas agreed by an appropriately qualified person. Spill kits will be provided in areas in all areas where liquids are stored and any refuelling areas.
- The local authority shall be informed immediately of any spillage or pollution incident that may occur on-site during the construction phase.
- All small plant will be positioned as far as practicable from watercourses. All small plant such as generators and pumps will be stood in drip trays, capable of holding 110% of their tank contents.
- All small plant will be positioned as far as practicable from the watercourses.
- Waste oils, empty oil containers and other hazardous wastes will be disposed of in accordance with the requirements of the Waste Management Act, 1996.

6.2.11. Site Tidiness & Housekeeping

- Construction works will be carried out according to a defined schedule agreed with the client and the relevant contractors, with regard to the hours of work outlined above. Any delays or extensions required will be notified at the earliest opportunity to the client and contractors;
- Contractors will ensure that road edges and footpaths are swept on a regular basis, this includes the local roadway adjacent to the northern boundary of the proposed development site;
- All contractors shall be responsible for the clearance of their plant, equipment and any temporary buildings upon completion of construction. The site will be left in a safe condition.

6.2.12. Inspection & Environmental Control & Monitoring

For the duration of the construction works a suitably qualified environmental clerk of works shall be employed to monitor the performance of prescribed mitigation measures.

The environmental clerk of works shall be independent of the main contractor and shall ensure that all proposed pollution control mitigation measures and environmental control measures are fully implemented and adhered to.

In addition, the Environmental Clerk of Works will complete routine inspections and monitoring of all construction activities and oversight of the mitigation measures in the Environmental Management Plan to ensure environmental compliance.

Regular inspections of all installed drainage systems will be undertaken, especially after heavy rainfall, to check for blockages, and ensure there is no build-up of standing water in parts of the systems where it is not intended.

A key function of the Environmental Clerk of Works will be to provide first-hand onsite identification, direction for intervention and immediate resolution of environmental issues as they arise.

Any drainage ditches within and adjacent to the boundary of the site are to be visually inspected on a bi-annual basis and additionally following the occurrence of any significant or extreme floods.

Surface water quality assessment and analysis of the Newtown Stream watercourse shall be undertaken for the duration of the construction stage and specifically following heavy rainfall events (i.e., weekly, monthly and event-based).

This shall involve the acquisition of surface water grab samples in the Newtown Stream just upstream and just downstream of the site. Surface water samples shall be sent to an accredited laboratory for analysis for the following parameters:-

BOD₅ (mg/l)

Total Suspended Solids (mg/l)

Total Petrol Hydrocarbons (TPH – mg/l)

pH

DO (mg/l)

Electrical Conductivity (S/m)

Temperature (°C)

Turbidity

It is proposed that water sampling and laboratory analysis shall be undertaken on a weekly basis for the duration of the construction stage of the project.

If any laboratory sample analysis results indicate that any of the above parameters are in exceedence of the 2009 Surface Water Regulations then all construction works shall be ceased immediately and the source of potential contamination shall be investigation. The local authority and Inland Fisheries Ireland shall also be informed if this scenario arises.

A project ecologist will prepare subject specific management plans to feed into the CEMP e.g. Invasive Species Mapping and Preparation of an Invasive Species Management Plan.

A critical early task of the CEMP will be to develop templates for the monitoring and reporting of environmental monitoring results, auditing, inspections and non-compliances. Reporting of all monitoring will be retained onsite with the Main Contractor or ECoW, or with the responsible specialist consultant

The CEMP will also establish templates for the reporting/auditing of mitigation measures, including: drawings and methodology for implementation of any necessary infrastructure (e.g. SuDS silt traps), frequency of inspection, details of personnel carrying out inspections, staff training details, reporting details (frequency/reporting chain and responsibilities).

A mobile 'Siltbuster' or similar equivalent specialist treatment system will be available on-site for emergencies in order to treat sediment polluted waters from any construction process should that occur.

Siltbusters are mobile silt traps that can remove fine particles from water using a proven technology and hydraulic design in a rugged unit. The mobile units are specifically designed for use on construction-sites. They will be used as final line of defence if needed.

6.2.13. Wastewater Management Plan

The expected uses of water during the construction phase are for the following purposes;

- Welfare use, maximum of 15 to 20 employees on the site at any one time;

For the duration of the construction phase, portable WC units or portable WC cabins will be in place within the proposed temporary construction compounds for welfare use as shown on *Drawing Number IE2816-CEMP-104-A, Appendix A*. These portable units or portable cabins will be self-contained and will be maintained on a weekly basis by an external licenced contractor. Disposal of wastewater from any portable WC unit or portable WC cabin will be the responsibility of the external licenced contractor.

There will be no discharge of effluent to groundwater or surface water during the construction phase. All wastewater from the construction facilities will be stored before removal off site for disposal and treatment. Disposal of the wastewater collected will be in accordance with the requirements of the Waste Management Act, 1996 and European Waste Catalogue (EWC) codes and be disposed of at a suitable licensed waste facility.

The details of the contractor who will be responsible for the removal of wastewater from the proposed development site will be provided to Wexford County Council on request.

6.2.14. Training and Toolbox Talks

The supervising ecologist / ECoW will prepare and deliver site induction or toolbox talks and training to all personnel, in liaison with the Resident Engineer or Site Manager. The ECoW will carry out supervision of all works during the construction phase of the project, together with pre-construction and construction phase ecological monitoring that may be required.

To this end, the ECoW will undertake a confirmatory site walkover survey, with the contractor site manager, in advance of the proposed works to determine and identify the following:

- Works deemed to be most at risk of rutting or ground compaction and resultant habitat loss;
- Suitability of works and access tracks for QI / SCI species such as waterbirds, and otter (not exhaustive);
- Suitability of works locations and access tracks for QI habitats and protected plant species particularly along the wet side of the embankment;
- Presence of invasive plant species along the proposed access tracks, construction locations and all ancillary works locations;

6.2.15. Biosecurity Invasive Species Best Practice Measures

Biosecurity is the prevention of disease causing agents entering or leaving any place where they can pose a risk to farm animals, other animals, humans, or the safety and quality of a food product.

There is potential that aquatic and/ or terrestrial invasive species (e.g. Japanese knotweed or giant hogweed) or pathogens (e.g. crayfish plague) may be accidentally introduced to a location via contaminated vehicles and equipment, in particular tracked vehicles, which were previously used in locations that contained invasive species. Adapted from the Irish Water Guidance (2016), the following best practice avoidance measures will help to contain and/or prevent the introduction of invasive species on a site as follows:

- Prior to arrival on site, the contractor's vehicles and equipment will be thoroughly cleaned and then dried using high-pressure steam cleaning, with water >65 °C, in addition to the removal of all vegetative material. Items difficult to soak/spray will be wiped down with a suitable disinfectant (e.g. solution of 1% Virkon® Aquatic);
- Evidence that all machinery has been cleaned will be required to be on file for review by the statutory authorities. The level of evidence required of the Contractor will be actual registration plates of vehicles onsite and a register of when, how and where each of these were cleaned before they arrived on site;
- Visual inspections will be carried out on all machinery and equipment for evidence of attached plant or animal material, or adherent mud or debris. Any attached or adherent material will be removed before entering or leaving the site, securely stored (away from traffic) for removal to an appropriate waste storage area the end of the work day;
- No removed material or run-off will be allowed to enter a water body of any sort;
- Following cleaning, all equipment and vehicles will be visually inspected to ensure that all adherent material and debris has been removed manually;
- Each field vehicle must carry a 'disinfection box'. This will contain Virkon Aquatic or another proprietary disinfectant, a spraying mechanism, cloths or sponges, a scrubbing brush and protective gloves. Protective gloves must be worn when using any disinfectant solution;
- Records of supplies and cleaning of delivery vehicles will be kept and regularly inspected by the ECoW;
- Spot checks on the adequacy of cleaning will be carried out by the ECoW;
- It is recommended to apply disinfectant to the undercarriage and wheels of any vehicles used after cleaning if the vehicles have been used in streams or rivers. (This does not apply to vehicle or machinery use in wetlands or peatland areas). Disinfectants must be used strictly in accordance with the manufacturer's instructions. They must be disposed of safely and never close to open waters such as drains etc.
- For any material entering the site, the supplier must provide an assurance that it is free of invasive species;

- Ensure all site users are aware of invasive species management plan, biosecurity and treatment methodologies. This can be achieved through “toolbox talks (See Section 6.3.6) “before works begin on the site;
- Adequate site signage, hoarding and fencing will be erected in relation to the management of non-native invasive species.

6.3. Construction Stage Waste Management

Waste generated as part of the construction stage is expected to be completely inert in nature and of minimal volume and will generally comprise of waste construction bricks and blocks and timber off-cuts. This material shall be temporarily stored within designated area within the temporary construction works compounds and shall be removed to a suitable licenced disposal facility.

No potentially contaminated waste shall be generated during the construction stage.

6.4. Operational Controls

It is not expected that any significant waste would be generated during the operation phase of the proposed 110kV development.

6.5. Drain & Watercourse Management Plan

For the duration of the operational lifetime of the proposed development, a Drain and Watercourse Management Plan shall be implemented.

The purpose of this management plan is to maintain the existing conveyance capacities of all drains and watercourses so as to ensure that any vegetation overgrowth or vegetation debris does not result in an increase flood risk to the site. The drain and watercourse management plan shall be implemented as follows:-

- *All drainage ditches adjacent to or beyond the boundary of the proposed 110kV substation development site to be visually inspected on a bi-annual basis and additionally following the occurrence of any significant or extreme flood events.*
- *Any vegetation overgrowth or vegetation debris within the drainage ditches that may impede flows in the ditches will be manually removal and disposed of as green waste.*
- *Where any vegetation debris (fallen trees, etc) is observed in the Newtown Stream following any extreme flood event, and where this debris cannot be manually removed, then the local authority and/or the OPW watercourse maintenance section shall be informed.*

The Drain and Watercourse Maintenance plan is intended to be a simple visual inspection plan and manual vegetation maintenance plan and will not involve any re-grading, re-profiling or any other excavation works within the existing drainage ditches nor will it involve any construction machinery. The activities undertaken as part of the Drain and Watercourse Management Plan shall therefore not result in any adverse impact to the receiving hydrological environment.

6.6. Archaeology

In the Archaeological Impact Assessment “AIA” that accompanied the planning application (See Appendix 3 of planning application submission), it is noted that there are no national or recorded monuments within or adjacent to the proposed development site. Lands immediately south were disturbed during the construction of the existing facility and the Greenlink Converter Station, while the construction of the rail line disturbed the lands to the north. Archaeological monitoring was previously carried out for the access road along which the grid connection will travel; and no archaeological material was identified. However, the subject site for the substation is greenfield in nature and as such mitigation measures have been recommended in order to assess the below ground potential. There are no associated stray finds from the Topographical Files and no increased archaeological potential was noted from cartographic or aerial photographic sources.

Recommendations for this project, include a comprehensive programme of archaeological test excavation across the footprint of the development in advance of construction. Following a grant of planning permission from Wexford County Council (LPA Ref. 20231294) for development of other electrical infrastructure within the footprint of the proposed development, and in accordance with Condition 11 attached to this permission, a licence application and method statement (See *Appendix C*) have been submitted to the adjudicating authorities and a licence granted to carry out testing within the footprint of the proposed development (Licence No. Ref. 24E0413). It is anticipated that this onsite work will take place in early April 2024 with a report on the findings to follow at the end of April 2024.




Figure 8 Proposed test trench layout

This report will assist the authorities to make an informed decision about the subsurface archaeological potential of the site. The report will include the testing results, all drawings and the location of any findings of an archaeological interest (if present). As per the mitigation measures provided in the AIA for this permission, all recommendations made in the testing report will be subject to the approval of the National Monuments Service of the DHLGH and the National Museum of Ireland. In addition to this, it is recommended that archaeological monitoring will take place during the site enabling and construction works that involve excavation and topsoil removal.

As stated in the impact assessment that accompanied the planning application the applicant is:

- Aware of the archaeological potential of the lands and its implications for the proposed development;
- Aware of the national policy for the protection of archaeological heritage and the Minister's stated preference for preservation in-situ and avoidance of impacts to archaeological heritage through design mitigation;
- Aware of the Local Authorities policies in relation to archaeological heritage as outlined in the development plan 2022-2028 and their obligations in accordance with the Planning and Development Acts (as amended);
- Aware of their obligations in relation to the further investigation of the site, if it is conditioned as such;

- Committed to fund whatever archaeological works are required in accordance with the National Monuments Acts (as amended) (including excavation, post-excavation analysis, conservation, and publication); and

Aware that the National Monuments Service, DHLGH will adjudicate on the results of the archaeological monitoring and will make recommendations to ensure the protection of the archaeological heritage.

6.7. Cultural Heritage – Landscape & Visual

In order to mitigate against any visual changes and to assist with the development blending into the existing hillside location, it is proposed that a comprehensive planting regime that includes the planting of native woodland species at the eastern end of the proposed development and the planting of a native hedgerow in front of the palisade fencing that runs along the engineered slope on the northern and eastern boundaries will take place. This will assist in mitigating any change in view from the western extent of Dunbrody Abbey (a National Monument located 1.6km east of the proposed development) towards the proposed development. Landscape planting has been approved under planning permission granted by Wexford County Council (LPA Ref. 20231294).

7. Decommissioning Process, Site Restoration and Monitoring Program

The following section presents elements of the decommissioning process, site restoration and implementation of a monitoring program to ensure works undertaken and completed at the decommissioning phase are successful.

The proposed potential pollution mitigation measures outlined below shall be implemented in accordance with the documentation below or more up to date documentation at the time of the decommissioning of the development site;

- *'CIRIA C532 – Control of Water Pollution from Construction Sites – Guidance for Consultants & Contractors' – CIRIA-2001.*
- *'CIRIA C648 – Control of Water Pollution from Linear Construction Projects – Technical Guidance – CIRIA 2006'*
- *Waste Management Act, 1996*
- *Best Practice Guidelines on the Preparation of Waste Management Plans for Construction & Demolition Projects. 2006*

7.1. Decommissioning Process and Time Scale

The following section outlines the infrastructure to be decommissioned, any potential environmental impacts and the options available for the materials arising. An estimated timeframe of the required work to be carried out is also presented.

110kV Substation & Associated Building

It is recommended that a designated area for the storage of materials (blocks, roofing material and electrical fittings, etc.) arising from the substation building during the decommissioning phase be constructed close to the western area of the site, using hardcore material laid on a suitable geotextile membrane. It is not anticipated that waste materials will be left on site.

The materials will be transported to the designated storage area and elements will be separated for recycling or reuse and temporarily stockpiled before being moved off-site.

Where feasible and applicable, the various materials can be sold for further use. If possible waste material will be sold, recycled or re-used. Materials that cannot be recovered will be appropriately categorized in accordance with the Waste Management Act, 1996 and European Waste Catalogue (EWC) codes and be disposed of at a licensed waste facility.

Care will be taken to ensure that dust and debris will be kept to a minimum and will not enter any watercourse nearby.

Any excavated area will be graded as required to reflect the natural contours of the land, if required, inert topsoil will be brought in from local sources, to backfill any voids. Any soil imported onto the site will be sourced from a certified supplier, in accordance with the Waste Management Act, 1996. The area will then be reseeded or re-vegetated with appropriate native species. This will also act in minimising the risk of soil erosion.

Timescale of work to be completed: 1 - 2 months.

IPP Building

It is recommended that a designated area for the storage of materials (blocks, roofing material and electrical fittings, etc.) arising from the IPP building during the decommissioning phase be constructed close to the western area of the site, using hardcore material laid on a suitable geotextile membrane. It is not anticipated that waste materials will be left on site.

The materials will be transported to the designated storage area and elements will be separated for recycling or reuse and temporarily stockpiled before being moved off-site.

Where feasible and applicable, the various materials can be sold for further use. If possible waste material will be sold, recycled or re-used. Materials that cannot be recovered will be appropriately categorized in accordance with the Waste Management Act, 1996 and European Waste Catalogue (EWC) codes and be disposed of at a licensed waste facility.

Care will be taken to ensure that dust and debris will be kept to a minimum and will not enter any watercourse nearby.

Any excavated area will be graded as required to reflect the natural contours of the land, if required, inert topsoil will be brought in from local sources, to backfill any voids. Any soil imported onto the site will be sourced from a certified supplier, in accordance with the Waste Management Act, 1996. The area will then be reseeded or re-vegetated with appropriate native species. This will also act in minimising the risk of soil erosion.

Timescale of work to be completed: 1 - 2 months.

Underground Cabling and Ducting

Excavation of the underground cabling and ducting will be completed in a manner that will minimise impact to the surrounding environment. A small excavator will be required to excavate the area surrounding the cables. The cables and ducts will be separate and where feasible material will be sold, recycled or reused.

It is expected to strip at least 0.5m width of topsoil to unearth the ducting and cables. The topsoil will be kept separate from other material whilst the ducting and cables are removed and the area will be backfilled using the excavated material. Any disturbance to the soil will require adequate backfilling and grading to match the contours of the surrounding land.

If required, inert clean topsoil and soil will be brought in from local sources, and the area will then be reseeded or re-vegetated with appropriate native species. Any soil imported onto the site will be sourced from a certified supplier, in accordance with the Waste Management Act, 1996.

Timescale of work to be completed: 1 - 2 months.

CCTV Cameras and Poles

The CCTV cameras will be dismantled from the mounted poles and removed to the designated area for classification and then onward for recycling, reuse or disposal at a licensed waste facility. Materials that cannot be recovered will be appropriately categorised in accordance with the Waste Management Act, 1996.




Figure 4 – CCTV Pole & Concrete Base

Similar to the removal of the steel stanchion, the support poles for the CCTV will be excavated and brought to the designated area for removal.

The concrete used at the base of the CCTV support pole, as illustrated in *Figure 4* above, will be crushed and temporarily stockpiled in the designated area before removal. CCTV ducting and cabling will be removed as per the section discussing underground cabling above.

Any disturbance to the soil will require adequate backfilling and grading to match the contours of the surrounding land. If required, inert topsoil will be brought in from local sources, and the area will then be reseeded or re-vegetated with appropriate native species.

Timescale of work to be completed: 1 month.

Perimeter Fencing

Any fencing that is not required for other future use on site will be dismantled and removed. The perimeter fencing will have small holes of between 250 and 300mm to allow for small mammals to enter and leave the site. All fencing materials will be separated and temporarily stored in the designated area for removal off-site. The separated material will be categorized for recycling, reuse and disposal as necessary.

Any disruption to the soil condition in the removal of the fencing will be backfilled and restored to its appropriate condition.

Timescale of work to be completed: 1 month.

Site Entrance, Stoned Area and Access Road

In the event that sections of the access road and stoned areas are to be decommissioned, the areas will be graded to match the surrounding contours. Any fill material that is required will be sourced locally and clean for use. Any soil imported onto the site will be sourced from a certified supplier, in accordance with the Waste Management Act, 1996. The area will also be reseeded or re-vegetated using appropriate native species.

Timescale of work to be completed: 1 month

Contamination

Strategies and mitigation measures similar to those employed during the construction phase as discussed in the relevant sections above, will be implemented for any potential disturbance (sedimentation, fuel spills, etc.) to key environmental features.

Where possible, materials will be reused or recycled. Waste materials for disposal will be removed by a licensed contractor and will be disposed of in accordance with the requirements of the Waste Management Act, 1996.

For the duration of the decommissioning phase any materials (eg. concrete, oils, fuels, cleaning agents, etc.) that require temporary storage will be stored in designated bunded areas.

Timescale of work to be completed: Duration of Decommissioning Period

Designated Storage Area and Sedimentation Protection

Following the removal of all materials related to the proposed development the designated storage area will be cleared, any base membrane will be removed for recycling or disposal and ground that is compacted or disturbed will be re-vegetated and graded to match the contours of the surrounding area.

Any area of contamination found (i.e oil spills etc.) will be assessed and remediated accordingly. Waste materials for disposal will be removed by a licensed contractor and will be disposed of in accordance with the requirements of the Waste Management Act, 1996.

Timescale of work to be completed: 1 month.

7.2. Site Restoration

Measures will be taken during the decommissioning phase to restore the sites of the proposed development to a state similar to its former condition or to a condition that is required for the future intended land use.

Due to the longevity of the project changes to habitat and vegetation may occur. Prior to the Decommissioning Phase, a site assessment will be completed to map and establish any sensitive areas or changes in habitat on the site that may potentially be impacted upon during the decommissioning phase. Measures can then be taken to minimise any detrimental effects that may occur.

Section 7.1 above outlines the elements required in decommissioning the various components of the proposed development, the anticipated restoration works that will need to be implemented and the approximate timescale for this work to be carried out.

Key restoration processes applicable during and post decommissioning of the proposed development are summarised in *Table 1* below;

Category	Action
Excavated areas	Any disturbances to the soil will be backfilled with clean inert soil. Topsoil will be placed over the area and graded to reflect the contours of the surrounding ground
Compacted ground	Areas that may become compacted by machinery are to be re-established through the reinstatement of topsoil and graded to match the contours of the surrounding ground.
Re-vegetation or reseeded of disturbed areas	Any areas that require re-vegetation are to be reseeded with native species consistent with the surrounding area.
Contamination	It is not expected that the lands surrounding the proposed development will require any special remediation since any hazardous materials (i.e. oil, fuel, cleaning fluids) used will be contained with adequate spill protection.
Erosion control	Measures to prevent soil erosion and runoff to sensitive watercourse can be implemented to assist with rehabilitation of the proposed development. This may include; <ol style="list-style-type: none"> 1. Adequate levelling and contouring of restored areas. 2. Appropriate use of vegetation to stabilise and enhance soil conditions.
Drainage system	The decommissioning of the proposed development will not require any alteration to existing drainage ditches, watercourses or any other hydrological features during the operation phase. Therefore there is no requirement to restore the pre-development drainage system.
Watercourse (e.g. Newtown Stream)	Decommissioning activities would not need to include the restoration of any water bodies.

Table 1 – Restoration Processes

7.3. Monitoring Programme

A periodic monitoring programme will be undertaken after the decommissioning of the proposed development to ensure that the above site restoration works discussed in *Section 7.1 and 7.2* are successful.

It is anticipated that the monitoring will be undertaken for at least two years after the decommissioning of the substation development is complete. A suitable qualified environmental professional will be engaged to oversee the monitoring program and initiated any further restoration works that will be required.

7.4. Inspection

Inspections by an appropriately qualified person will be carried out during decommissioning phase to certify that the measures detailed above are being implemented effectively and, if required, removal of materials from the site will be halted and corrective action taken.

8. Summary Conclusions & Recommendations

This preliminary planning stage Construction Environmental & Management Plan (CEMP) has been prepared in order to ensure that the highest feasible level and robust methods of pollution mitigation and environmental control measures are implemented before and during the construction stage of the proposed 110kV substation development and during the operational and decommissioning phase.

For the duration of the construction works a suitably qualified ecological supervisor shall be employed.

The ecological supervisor shall be independent of the main contractor and shall ensure that all proposed pollution control mitigation measures and environmental control measures are fully implemented and adhered to.

On-going inspection of all pollution mitigation measures and environmental controls shall be undertaken by the ecological supervisor.

In consideration of the proposed mitigation measures presented in this preliminary CEMP, the impact to the existing environment due to the proposed development shall be negligible.

It is recommended that updates be made to the CEMP every five years from the date of preparation until decommissioning and site restoration is complete. Review and revision of the Construction Environmental Management Plan is the responsibility of the facility operators, or any subsequent owners of the facility.

9. References

BS5228-1:2009 - Code of practice for noise and vibration control on construction and open sites – Part 1: Noise – British Standard (2009)

CIRIA C532 – Control of Water Pollution from Construction Sites – Guidance for Consultants & Contractors’ – CIRIA (2001)

‘CIRIA C648 – Control of Water Pollution from Linear Construction Projects – Technical Guidance – CIRIA 2006’

Ecological Impact Statement (September 2023) Great Island Power Development – Moore Group Environmental Services

TLI Group – Construction Methodology – Kilmannock 110kV Grid Connection & Substation (September 2023)

Environmental Protection Agency (EPA), <http://gis.epa.ie/map>. Accessed: October 2020

Geological Survey of Ireland, www.gsi.ie. Accessed: September 2023

Waste Management Act, 1996

Best Practice Guidelines on the Preparation of Waste Management Plans for Construction & Demolition Projects. (2006)

Appendices

Appendix A. Drawings

IE2816-001-C	Site Location
IE2816-CEMP-102-B	Location of Designated Watercourse
IE2816-CEMP-104-A	Temporary Construction Compound Layout Plan




SITE LOCATION

IE Consulting Innovation
 Centre, Green Road,
 Carlow, R93 W248.
 Ph: 059-9133084
 E-mail: info@iece.ie
 Web: www.iece.ie



Project Title:	CEMP				
Project Address:	GREAT ISLAND, LIKMOKEA, CO. WEXFORD				
Client:	KILMANNOCK BATTERY STORAGE LTD.				
Drg. Title:	SITE LOCATION MAP				
Dwg. Scale:	Date:	Dwg.No:	Job No:	Revision:	Dwg.By:
1:50,000	13/12/23	IE2816-001	IE2816	C	LMC



Location of Hydrocarbon Interceptor

Proposed Development Site Boundary

Works Compound

Newtown Stream

Ditch

Newtown Stream

Ditch

LEGEND

	SITE BOUNDARY
	WORKS COMPOUND
	RIVER
	EXISTING DRAINAGE DITCH

B	14.12.23	PLANNING		Lmc	PMS
A	19.09.23	PLANNING		Lmc	PMS
rev.	date	amendment		drm	ckd

PROPOSED DEVELOPMENT AT
GREAT ISLAND, LIKMOKEA,
CO. WEXFORD

CONSTRUCTION ENVIRONMENTAL
MANAGEMENT PLAN

PROPOSED LOCATION OF DESIGNATED
STORAGE AREA AND WATERCOURSES




IE CONSULTING
WATER-ENVIRONMENTAL-CIVIL

CARLOW OFFICE:
INNOVATION CENTRE
GREEN ROAD
CARLOW, R93 W248

NEWRY OFFICE:
7 LINENHALL
WIN BUSINESS PARK
NEWRY, BT35 6PH

file location:	N:\IE2816\DRAWINGS	scale:	1:3,500	AS
drawing status:	PLANNING	datum:	MALIN	
drawing no.	IE2816-CEMP-102	drawn:	Lmc	
rev	B	checked:	PMS	
		approved:	PMS	
		date:	19.09.23	

© IE Consulting. This drawing or its contents must not be reproduced for any purpose without written permission. It is to be used only for the purpose for which it is supplied.



LEGEND

rev.	date	amendment	drn	ckd
A	20.09.23	PLANNING	LMc	PMS

PROPOSED DEVELOPMENT AT
GREAT ISLAND, LIKMOKEA,
CO. WEXFORD

CONSTRUCTION ENVIRONMENTAL
MANAGEMENT PLAN

PROPOSED CONSTRUCTION
COMPOUND LAYOUT

CARLOW OFFICE: INNOVATION CENTRE, GREEN ROAD, CARLOW, R93 W248
 NEWRY OFFICE: 7 LINENHALL, WIN BUSINESS PARK, NEWRY, BT35 6PH

file location:	N:\IE2816\DRAWINGS	scale:	1:200
drawing status:	PLANNING	datum:	MALIN
drawing no.	IE2816-COMP-104	drawn:	LMc
rev	A	checked:	PMS
		approved:	PMS
		date:	20.09.23

© IE Consulting. This drawing or its contents must not be reproduced for any purpose without written permission. It is to be used only for the purpose for which it is supplied.

Appendix B. Typical Wheel Wash Details



Wheel Washing

Keeping roads clear of dirt and debris is essential for the safety of road users and the environmental control of mud and other substances. Powerful and heavy-duty wheel-wash solutions from Garic guarantee an efficient, sanitary and recyclable wash to keep your roads clear and your wheels clean.



Enviro Wheel Wash



Dims (L X W) (Feet)	Min Hire Period
Total Area Required Excluding Entry And Exit Of Wash	
22 X 24 Without Ramps	1 Week
66 X 24 With Ramps	1 Week

Our fully automated and totally self-sufficient enviro wheel wash is perfect for sites where sticky clay and mud can be a big problem. As vehicles pass through the wheel wash, exceptionally powerful jets spray water onto the wheels, chassis and undersides, cleaning the vehicles without them even needing to stop. The enviro wash recycles and re-circulates 100% of water separating the muck and debris in the lagoon area for easy removal and cleaning.

- Powered heavy duty wheel wash
- Steel fabricated wash area
- Removable rumble road sections
- Heavy duty lifting and lashing points
- Lagoon with vertical spray jets
- Magic eye system

ADD ONS

- ✓ Electric pumps
- ✓ Water tanks

Elevated Enviro Wheel Wash



The Enviro wheel wash can also be elevated and placed directly onto a surfaced area with ramps; perfect for quick set-up and removal on short-term contracts or sites that require heavy duty wheel washing. The Enviro wash recycles and re-circulates 100% of water separating the muck and debris in the lagoon area for easy removal and cleaning.

- Powered heavy duty wheel wash
- Steel fabricated wash area
- Surface mounted no excavation required
- Removable rumble road sections
- Heavy duty lifting and lashing points
- Lagoon with vertical spray jets
- Magic eye system
- Interceptor drip tray as standard
- 30' ft. external galvanised steel ramps

ADD ONS

- ✓ Electric pumps
- ✓ Water tanks



Dims (L X W) (Feet)	Min Hire Period
22 X 24 Without Ramps	1 Week
82 X 24 With Ramps	1 Week

Drive Through Bath



Dims (L X W) (Feet)	Min Hire Period
35 X 12 Without Ramps	1 Week
77 X 12 With Ramps	1 Week

Garic's unpowered drive through bath is an inexpensive yet very efficient vehicle wash system. It is ideal for sites that have moderate mud and dirt and is quick and easy to install.

Trucks, dumpers and lorries are cleaned as they drive over a series of rumble strips which shake off the heaviest earth. They are then washed as the wheels, chassis and undersides pass through a water lagoon to provide a quick, safe and effective cleaning system. If required, extra road rumble strips are available.

- Steel fabricated wash area
- Removable rumble road sections
- Heavy duty lifting and lashing points

ADD ONS

- ✓ Ramps
- ✓ Water tanks



Appendix C. Archaeological Testing – Method Statement

Method statement to accompany a licence application for archaeological testing at site at Great Island, Co. Wexford

Applicant: Liam Coen c/o Courtney Deery Heritage Consultancy, Lynwood House, Ballinteer Road, Dublin 16

lcoen@courtneydeery.ie

Date: 11th March 2024

1 Introduction

1.1 General

It is proposed to carry out pre-construction archaeological testing at a site in fulfilment of grant of planning. The development consists of the construction of a battery energy storage system (BESS), 38kV substation and associated cabling at Great Island, County Wexford under planning ref. 20231294 Wexford Co. Co. It is proposed to excavate two evenly spaced trenches, 250m in length each, in order to determine the presence and nature of archaeological remains within the site.

1.2 Site Location

The site is located within the townland of Great Island (Parish of Kilmokea, Barony of Sherburne, Co. Wexford, 6" OS map 39; ITM centre of site 669237, 615120) and lies to the east of an existing power plant facility (**Figure 1**). The main body of the site is greenfield and located to the south of what was historically known as the Fishguard & Rosslare Railway Line. The cable trench largely runs along previously disturbed grounds.




Figure 1: Site Location Map

1.3 The Proposed Development

The permitted development (Figure 2) is for an electrical installation on 2.6Ha. of lands within the townland of Great Island, Co. Wexford. The development can be described as:

Construction of an electrical infrastructure installation and associated underground grid connection (UGC) on lands within the townland of Great Island measuring approximately 2.6Ha. in overall area. The installation will consist of a Battery Energy Storage System (BESS), a 38kV substation and associated ancillary development. The BESS would comprise 16no. individual battery storage units on concrete foundations, each measuring 2.60m in overall height, 2.4m in width and 6.00m in overall length with heating, ventilation, and air-conditioning (HVAC) units.

The 38kV substation would consist of a 38 kV transformer; diesel generator, house transformer; disconnect, individual current and voltage transformers, combined current/voltage transformer, surge arrestors; circuit breakers; cable sealing end, and substation building with an overall footprint of 66.00sqm; a blast wall measuring 8.00m in overall height; 2no. lightning masts measuring 18.00m in overall height; palisade fencing measuring 3.00m in overall height; pole-mounted security cameras and lamp posts.

The typical UGC installation would consist of standard ESB ducting details of the following 1no. trench (0.6m wide; 1.22m deep) measuring approximately 724m in overall length to carry 3no. 110mm power ducts and 2no. communication ducts, connecting the substation to an existing 38kV ESB substation at Campile. The typical trefoil trench will need to be adapted to a flat formation to accommodate for any service crossings encountered along the route. A typical width of trench for a flat formation trench would be approx. 1.15m with vary depths.

Ancillary development consists of a 6.00m wide access road off an existing road to the Greenlink substation; levelling of site to create 2 No. platforms at +16.00m and +12.00m ASL; retaining wall to facilitate reduction of site levels along southern and south-western boundaries; an earthen bund on the north and eastern boundaries; and all other associated works, including landscaping proposals. A temporary construction compound would be constructed within the site boundary for construction phase of the development, after which it would be removed.

Battery energy storage system (BESS) & 38kV substation
 Great Island, County Wexford
 Archaeological Testing




Figure 2 Proposed development plan

1.4 Archaeological Condition

Extract from Grant of Planning (ref: 20231294 – Condition 11).

11. • The applicant is required to engage the services of a suitably qualified archaeologist to carry out a documentary and field based archaeological assessment of the development site. No sub surface work should be undertaken in the absence of the archaeologist without their consent.

• The assessment shall involve documentary and cartographic research, an analysis of all previous archaeological assessments carried out in the area (including the desk based assessment submitted with the application, carried out by Rubicon Heritage), geophysical survey, fieldwork, archaeological testing (licence under the National Monuments Acts 1930-2014) and an examination of the proposed plans/design details for the development.

• The archaeologist shall prepare and submit a written report, including an archaeological impact statement and mitigation strategy, to the Planning Authority and to the Department of Housing, Local Government and Heritage as further information. Where archaeological material/features are shown to be present, avoidance, preservation in situ, preservation by record (excavation) and/or monitoring may be required. Mitigatory measures to ensure the preservation and/or recording of archaeological materials/features shall be suggested in the archaeological assessment report. The Department of Housing, Local Government and Heritage and the Planning Authority will advise accordingly following receipt of the archaeological assessment.

REASON:

In the interests of identifying/preserving any archaeological features.

It should be noted that the desk based assessment submitted with the planning application under ref. 20231294 was produced by Courtney Deery Heritage Consultancy Ltd. rather than Rubicon Heritage as stated in the planning condition above.

2 Archaeological & Historical Background

2.1 Prehistory Activity (c. 7000 B.C. – A.D. 400)

There are no monuments of a prehistoric nature recorded within or immediately adjacent to the development area. Evidence for finds and prehistoric material is a result of archaeological investigations that have taken place in association with development. During the construction of a gas pipeline in the townland of Great Island, a stone tool assemblage (Sternke, 2012) including Neolithic struck flints and a hammer stone were retrieved, indicating Neolithic activity in the area. Work associated with the construction of the gas pipeline also revealed two pieces of prehistoric pottery and a fulacht fia (a Bronze Age cooking site), this was fully excavated (12E0392).

2.2 Early Medieval Period (400 A.D. – 1169 A.D)

Improvements in agriculture from the 5th century AD resulted in a further wave of settlement expansion and population increase in Ireland, leading to the construction of the modern landscape's most common archaeological site; the ringfort, referred to in contemporary documentary sources as *rath*, *lios* or *caiseal*. Ringforts are generally circular enclosures, essentially habitation sites or farmsteads, typically between 30-60m in diameter. They often contain the remains of house structures, pits or internal subdivisions, while cereal-drying kilns and annexed field enclosures are frequently found immediately outside of them.

There is one large scale enclosure that is located to approximately 700m northwest of the development. This is marked as a circular embanked enclosure (ext. diam. c. 100m) (WX039-028004) on the 1839 ed. of the OS 6-inch map and as an oval feature (dims c. 150m N-S; c. 100m E-W) on the 1940 ed. It is situated on gentle south and west-facing slope. The site presents as an oval grass-covered area approximately 100m northeast-southwest by 60m northwest-southeast and is defined by banks of various heights ranging from half a metre to one metre. There is no

visible trace of an entrance, but Major's Well, a natural spring is located inside the perimeter at the southwest and is annotated on historic OS maps.

2.3 Medieval Period (1169 – 1540 A.D.)

Dermot Mac Murrugh, the ousted king of Leinster, granted two cantreds to Hervey de Montmorency in 1169 'adjoining the sea between Wexford and Waterford', which included Great Island, and Hervey granted land from this to the Cistercian abbey of Dunbrody (WX039-030001-) which he founded in 1171-5 and which is c. 1.6km east of Great Island. The island became the centre a large manor, the accounts of which survive for the 1280s and 1290s (Hore 1900-11, vol. 3), and these record the repair of a castle in the 1280s, which included the digging of a moat. Located at the top of a severe west-facing slope of what was once the Great Island overlooking the River Barrow. However, the channel (With c. 500-600m) around the northeast and east sides of the island is long silted up and reclaimed.

An arcing earthen bank survives and this bank backs on to the steep west facing slope down to the river. If complete it would enclose a D-shaped area, approximately 250m east-west by 200m north-south, most of which would be on the slope. The interior is grass-covered but with a large number of modern buildings. This may be the last physical remnants of a ringwork castle (WX 039-028001) erected by Harvey de Montmorency shortly after the initial grant. Within the enclosure are the traditional sites of two castles (WX039-028002; WX039-028003) and the traditional site of a leper hospital (WX039-028005-).

2.4 Post Medieval

At the time of the mid-seventeenth century Down Survey, Great Island was shown as an island within the River Barrow/ Nore forming part of the boundary between Wexford, Kilkenny and Waterford. A single stone castle was shown to be located on these lands (Figure 3).

2.5 Cartographic sources

The first edition Ordnance Survey (OS) six-inch map was published in 1841 (Figure 4). It clearly shows Great Island as a peninsula surrounded on three sides by water. The large enclosure is easily recognisable to the north as a circular hachured feature and a cluster of structures are shown in and around the medieval stronghold. Where the power plant facility is now located is shown as a series of fields and the development site is located in an area shown as one large field bounding the channel carved by the River Barrow and the River Nore. The subject site comprises a series of agricultural fields with no buildings, features or structures depicted within the site.



Figure 3 Extract from Down Survey Barony map of Wexford




Figure 4 First edition six inch Ordnance Survey map (1839-41) showing site in red and cable route in blue

The later 25-inch OS map from 1905 shows little change and is not as detailed as the previous 6-inch map. Again, the subject site is still depicted as two agricultural fields (Figure 5)




Figure 5 Historic 25 inch OS map (1905)

2.6 Summary of Previous Investigations

Archaeological investigations have taken place in Kilmokea located at the northern end of Great Island townland but no archaeological features were revealed (Licence Number 10E126). In 2002 a ditch and a bank appeared to represent the enclosure earthworks at Kilmokea (Licence Number 02E0071). Further testing was carried out as predevelopment work for a proposed gas pipeline in 2011 (Licence Number 11E0342 and 11E0339) and no features of potential archaeological significance were apparent in the trenches.

Monitoring of topsoil stripping for the Bord Gáis Networks Gas to Great Island scheme took place in 2012-2013. The pipeline construction commenced at an existing above ground installation at Baunlusk, Co. Kilkenny and extended to the Endessa Power Station at Great Island, Co. Wexford. The pipeline was 46km long and numerous sites were revealed including a Neolithic stone assemblage, burnt stone spreads, troughs, pits and twenty stake holes (sites 34-3 and 3), a prehistoric hearth, post hole and eight stake holes (site 34-1), two pits, one with prehistoric pottery pieces (Roche and Grogan 2012) and two post holes (site 33-1) and burnt spreads and a fulacht fiadh (site 33-2) in Great Island townland (Licence Numbers 12E0356, 12E0395, 12E0393 and 12E0392).

In 2012 archaeological monitoring (Licence Number 12E0122) took place within the confines of the existing power facility which occupies an area of 58ha. Groundworks associated with the

development were undertaken in three main areas: the entranceway and access road to the development site, a large area to the north-east of the existing power plant to be used for storage and an area of reclaimed ground to the immediate east of the existing plant where the new CCGT plant was constructed. The works were largely within brownfield areas of the site. No archaeological features, finds or material were revealed (McCarthy 2012).

In addition, to the investigations above the most recent and closest archaeological work took place in 2021 and 2022 at the site of the converter station immediately to the south of the development. A geophysical survey was carried out by Wessex Archaeology (Licence Ref 21R0315) and detected several pit and ditch like anomalies suggestive of an archaeological origin. The results of the gradiometric survey were used to finalise the layout of the archaeological test trenches. Seventeen test trenches were proposed but due to ground conditions, the presence of overhead lines and a gas pipeline wayleave, this was altered on site and fourteen trenches were dug (Licence Ref. 21E0854) (Figure 6). The test excavation did not encounter any evidence of prehistoric activity on the site. Neither is there any evidence to suggest any medieval domestic or industrial activity associated with any known settlement on Great Island, it was concluded that historically the site had been used for pasture. The geophysical anomalies were found to be degraded and weather rock outcrop, natural and not archaeological in origin.

A visual assessment was conducted to and from Dunbody Abbey, a national monument located approx. 1.6km east of the development. It was concluded that the location, and operation of the development would not detract in a significant manner from the setting and views from the abbey (Entrust 2023).




Figure 6 Test trench layout at Converter site

2.7 Recorded Monuments and Designated Sites

The existing power station at Great Island, including the BESS development, is located to the south of a medieval settlement complex consisting of two castles (WX039-028002, WX039-028003), an enclosure (WX039-028004) and a leper hospital (WX039-029005); the closest of which being the enclosure that lies c.650m to the north-west (Figure 7)

There are no RPS or NIAH sites located within the development site or immediately adjacent to it. The closest structure on the RPS is Kilmokea House, RPS ref. WCC0882 and it is located c. 1.5km to the north of the subject site.

There are no national monuments within or in the vicinity of the development site. The closest national monument is Dunbrody Abbey (National Monument Number 192 and WX039-030001), a Cistercian house located just over 1.6km to the east of the development.




Figure 7 Surrounding RMP / SMR sites

3 Project Strategy

Evenly spaced trenches will be excavated in order to determine the presence and nature of any archaeology that may exist within the site. Trenches will be mechanically excavated by a 13 tonne tracked excavator (or similar) fitted with a grading bucket and under constant archaeological supervision. Trenches will be excavated in 0.2m spits to the top of potential archaeological deposits or the natural subsoil, whichever is encountered first. Potential archaeological features will be assessed, then cleaned and a hand-dug test slot excavated if deemed necessary. Features will be assigned a unique number and a full written and digital photographic record will be maintained. All features will be recorded using a GPS device. If any archaeological features are identified, then further trenches may be excavated to establish the nature and extent of the archaeology. While all trenches will be re-instated after excavation, any archaeological features identified will be covered with a protective layer of plastic pending the agreement with the relevant authorities for appropriate mitigation measures.




Figure 8 Proposed test trench layout

4 Project team & duration

Archaeological testing will be undertaken by a licensed director, Liam Coen. It is anticipated that the excavation will take one or two days to complete.

5 Finds Retrieval

Finds will be retrieved through visual inspection of exposed surfaces, excavated trench spoil and during any hand-excavation that may take place. Any finds will be recorded by context, individually bagged where necessary, catalogued and given a finds number. Find numbers will be assigned and labels applied to finds in line with the NMI Standards for the Care and Treatment of Archaeological objects from Excavations 2022 guidelines. The NMI will be consulted in the case of there being doubts as to what constitutes an archaeological object worthy of retention. The unanticipated discovery of human remains will be reported as soon as possible to the NMS and the NMI. All finds will be stored at the offices of Courtney Deery Heritage Consultancy during monitoring and during post-excavation works and ultimately will be deposited with the National Museum of Ireland for permanent storage.

6 Specialists / Conservation

In the event of particularly fragile objects or sensitive materials being uncovered a relevant specialist or conservator will be called for advice or to assist on site. Items which are at risk of deteriorating will be brought to a conservator without delay.

In the event that human remains are uncovered an osteo-archaeologist will be made available. Each specialist will have a relevant post-graduate qualification. These may include:

Human remains: Denise Riordan / Maeve Tobin

Animal remains: Emily Murray

Environmental analysis, wood and charcoal ID: Ellen O' Carroll

Prehistoric Pottery: Eoin Grogan & Helen Roche

Medieval pottery: Clare McCutcheon

Lithics: Dermot Moore / Conor Brady

Conservation: Susannah Kelly

7 Sampling strategy

Bulk soil samples are not envisaged being taken during the course of testing. However, if exceptional circumstances warrant it, then samples may be taken, if deemed necessary for the recovery of potential human bone or artefacts.

8 Post Excavation

The developer has been made aware of his responsibility to provide adequate funds to cover all post-excavation and specialist costs associated with the archaeological monitoring. A letter has been provided confirming the availability of funding for this purpose.

The site archive, and any finds, samples etc. would be kept in safe storage during the post-excavation stage. All necessary conservation would only be undertaken by a professional conservator. All finds will ultimately be housed in the National Museum.

9 The Report

A written report will be compiled that will set out the results of the archaeological testing. This will be submitted to the Licensing Section of The National Monuments Section – The Heritage Service, and the National Museum of Ireland. A summary of the report would also be submitted to the Excavation Bulletin within 6 weeks of the end of fieldwork. Should results warrant it, wider dissemination in the form of full publication may be recommended.

10 References

CDHC, 2023. Archaeology, Architecture and Cultural Heritage Report: 38kV Substation and Battery Energy Storage System (BESS), Great Island, Co. Wexford

Entrust, 2023. Great Island, Kilmokea, Co Wexford, Installation of 8kV electrical installation – Landscape and Visual Impact Assessment.

McCarthy, M. 2012. Archaeological monitoring of a natural gas-fired combined cycle gas turbine (CCGT) for Endessa Ireland Ltd. Licence Ref 12E0122, unpublished report.

Roche, H. and Grogan, E. (2012) The prehistoric pottery from Great Island, Co. Wexford. Unpublished report.

Sternke, F. 2012. Stone finds from Site 34- 2 & 3. 12E0396. Great Island, Co. Wexford. Unpublished report.

Wessex Archaeology, 2021. Geophysical survey of Great Island (Licence Reference 21R0315).

Online Sources

www.archaeology.ie

www.askboutireland.com (Griffith's Valuation)

www.buildingsofireland.ie (NIAH)

www.downsurvey.tcd.ie

<https://www.dri.ie> (Digital Repository of Ireland)

www.excavations.ie

www.heritagemaps.ie

www.maps.osi.ie

**Appendix 2 –
Addendum letter to Transport Management Plan submitted under
Application ABP Ref. 318914-24 (prepared by Local Transport Projects
Ltd.)**

PROPOSED 110kV SUBSTATION, GREAT ISLAND, COUNTY WEXFORD

RESPONSE TO TII (16/04/2024)

1. Introduction

- 1.1 Local Transport Projects Ltd (LTP) previously produced a Traffic Management Plan (TMP) (LTP, 2023) in support of a planning application to (Ref: ABP-318914-24) to An Bord Pleanála (ABP) for a proposed 110kV electrical substation and 110kV underground grid connection (UGC) on land at the townland of Great Island in County Wexford.
- 1.2 The local planning and roads authority for the site is Wexford County Council (WCC).
- 1.3 The proposals represent Strategic Infrastructure Development (SID), and therefore a response to the planning application was provided by Transport Infrastructure Ireland (TII) with respect to the impact of the scheme on the national roads. This letter has been produced to provide a response to the TII observations (Tara Spain, 26/01/2024) on behalf of the Applicant.
- 1.4 On behalf of the Applicant, LTP engaged with WCC Roads Department (David Murphy) in August/September 2023 to ascertain their views on the proposed construction routing for electrical infrastructure development at Great Island, Kilmokea. This development included that recently granted planning permission and currently under consideration by WCC (LPA Refs. 20231294 and 20240309 respectively), as well as the proposal under consideration by ABP in this application. In all instances no concerns over structures or routing along the regional/national roads were raised.

2. Port of Entry

“In relation to the proposed delivery to site, TII [sic] observes the use of N25 national roads from a port of entry which is unclear.” (TII – Tara Spain, 26/01/2024)

- 2.1 It is confirmed that the expected port of entry for any abnormal load deliveries to the site would be Rosslare Harbour. This port of entry and the associated transportation route to the site (along the N25-R733-L4033) are the same as one of the two approved routes for the adjacent Greenlink Interconnector facility by Siemens (Ref: 308906), as detailed in the supporting Environmental Impact Assessment Report (EIAR) (ARUP, 2020).

3. Proposals for Abnormal Loads

“TII is unable to ascertain the proposed treatment to address abnormal ‘oversized’ loads in the documentation submitted. TII notes that the Transport Management Plan refers to approaches for numerous other similar projects within the vicinity of the proposal.

TII advises that any operator who wants to transport a vehicle or load whose weight falls outside the limits allowed by the Road Traffic (Construction Equipment & Use of Vehicles) Regulations 2003, SI 5 of 2003, must obtain a permit for its movement from each Local Authority through whose jurisdiction the vehicle shall travel.” (TII – Tara Spain, 26/01/2024)

- 3.1 The submitted Traffic Management Plan (TMP) (LTP, 2023) confirms the proposed routing for abnormal loads in Section 3.2, with swept path analysis for the Abnormal Indivisible Load Vehicles (AILVs) delivering these abnormal loads considered in Section 3.3, with the proposed traffic management measures (for AILVs and smaller vehicles) outlined in Section 5.
- 3.2 The required procedures for hauliers to follow before delivering any abnormal loads is noted and agreed. At this planning application stage, a haulier has not been appointed, although the procedural requirements will be reaffirmed with the appointed haulier in due course. For clarity, the proposed route for any abnormal load deliveries only travels through one local authority, Wexford County, and the scheme has been discussed with WCC Roads (David Murphy), with no concerns raised to date over the wider route along the regional/national roads.

4. Impact on Structures

“A full assessment by the applicant/developer of all structures on the national road network along the delivery route should be undertaken, where relevant, to confirm that all structures can accommodate the proposed loading associated with the delivery of components to site where the weight of the delivery vehicle and load exceeds that permissible under the Road Traffic Regulations. The Authority requests referral of all proposals agreed between the road authorities and the applicant impacting on national roads”. (TII – Tara Spain, 26/01/2024)

- 4.1 It is understood that the weight of the abnormal load components to be delivered to the proposed site is less than those associated with the approved adjacent Greenlink Interconnector facility (Ref: 308906), therefore it is expected that the same route from Rosslare Harbour would also be suitable for the proposed scheme in terms of the impact on structures along the route.
- 4.2 No concerns over structures along the regional/national roads along the route have been raised to date by the only affected road authority (WCC, David Murphy).
- 4.3 If deemed necessary, the Applicant would be willing to accept a pre-commencement planning condition to undertake further structural investigations.

5. Proposed Works

“Any proposed works to the N25 national road network to facilitate component delivery to site shall comply with TII Publications and shall be subject to Road Safety Audit as appropriate”. (TII – Tara Spain, 26/01/2024)

- 5.1 These requirements are noted by the Applicant. At this stage, it is not envisaged that any works will be required to any national roads associated with the proposed scheme.

6. Road Damage

“Any damage caused to the pavement of the existing national road due to the turning movement of abnormal ‘length’ loads (e.g. tearing of the surface course) shall be rectified in accordance with TII Pavement Standards and details in this regard shall be agreed with the Road Authority prior to the commencement of any development on site”. (TII – Tara Spain, 26/01/2024)

- 6.1 These requirements are noted by the Applicant. If deemed necessary, the Applicant would be willing to accept a pre-commencement planning condition for the submission and agreement of details on road damage rectification.

7. Duplicate Comments

“Any operator who wants to transport a vehicle or load whose weight falls outside the limits allowed by the Road Traffic (Construction Equipment & Use of Vehicles) Regulations 2003, SI 5 of 2003, must obtain a permit for its movement from each Local Authority through whose jurisdiction the vehicle shall travel. TII considers that it is critical a full assessment by the applicant/developer of all structures on the national road network along the haul route should be undertaken, where relevant, and all road authorities along the haul routes should confirm their acceptance of proposals by the applicant”. (TII – Tara Spain, 26/01/2024)

- 7.1 The procedure for abnormal load deliveries is discussed in relation to the same comment in Section 3, with the impact on structures discussed in relation to the same comment in Section 4. It is reiterated that the proposed route for any abnormal load deliveries only travels through one local authority, Wexford County.

8. References

ARUP (Ove Arup & Partners Ireland Ltd), 2020. Environmental Impact Assessment Report – Ireland: Onshore.

LTP (Local Transport Projects), 2023. Proposed 110kV Substation, Great Island, County Wexford – Traffic Management Plan (Final Issue 1, 18/12/2023).